

Tender No. []

1.0 GENERAL

1.1 SUBMITTALS

- .1 Provide the following submittals.
- .2 Permits and authorizations for burning debris prior to performing such work.

2.0 PRODUCTS – NOT USED

3.0 EXECUTION

3.1 PREPARATION

- .1 Protect trees, shrubs, and other vegetation within the specified site clearing and grubbing areas that are designated to remain in place, against unnecessary cutting, breaking, and any other damage.
- .2 Protect from damage, fences, roadways, and other existing site improvements within the specified site clearing and grubbing areas that are designated to remain in place.
- .3 Protect survey reference points from damage.

3.2 REMOVAL

- .1 Remove all logs, trees, brush, stumps, roots, and other deleterious material from the specified areas except for trees or vegetation designated to be preserved.
- .2 Remove all roots and other deleterious materials to 300 mm below the ground surface.
- .3 Remove tree branches that extend into the specified clearing area and which hang within 6 m of the finished grade, by cutting them off close to the trunk.
- .4 For trees that are designated to remain, cut only roots or branches that interfere with the Permanent Work and treat the roots or branches with a non-toxic horticultural emulsion authorized by the Minister.
- .5 Finish the cleared areas to a neat and levelled condition.

3.3 DISPOSAL

- .1 Obtain applicable permits and authorizations prior to burning any debris at the Site. When permitted by Regulatory Requirements, burn combustible materials on Site in a burn pit authorized by the Minister.
- .2 Provide continuous supervision of the burning operation and use burning methods that do not place surrounding vegetation and property at risk.

Tender No. []

- .3 Backfill burn pits with a minimum cover of 1 m of mineral soil. Level and finish to a neat condition.
- .4 When burning is not permitted by Regulatory Requirements, load, transport, and dispose of debris at the specified on-Site waste disposal areas or at an off-Site waste disposal facility.
- .5 Consolidate logs, trees, stumps, roots, and other deleterious material to the highest degree practicable and cover with a minimum of 1 m of mineral soil. Level and finish to a neat condition.

END OF SECTION