# 53.2 PIT-RUN GRAVEL

### 53.2.1 GENERAL

The Work consists of placing pit-run gravel on gravel surface roadways or in excavations for pavement patching or culvert installations or at any other areas specified by the Engineer.

### 53.2.2 MATERIALS

The Contractor shall pick up pit-run gravel from a source designated by the Engineer or supply designation 6, class 125 pit-run material in accordance with Specification 55.3, Aggregate Production and Stockpiling and Specification 55.4, Supply of Aggregate.

In lieu of the designation 6, class 125 material, the Contractor may use a select, free draining material with a maximum top size of 125 mm, provided such material is satisfactory to the Engineer.

## 53.2.3 PROCEDURE

Pit-run material shall be placed on the prepared area or in an excavation in a uniform manner and quantity, which will produce the required compacted thickness and width designated by the Engineer.

### 53.2.4 TIME TO COMPLETE AND SCHEDULING OF WORK

The Contractor shall complete the Work within 60 calendar days of the issuance of the Work Order. This work shall be performed immediately following the excavation or preparation of the area to be treated with pit-run. The Contractor shall diligently complete all aspects of the Work.

### 53.2.5 MEASUREMENT AND PAYMENT

### 53.2.5.1 General

Measurement will be in cubic metres based on truck box measurement.

Payment for hauling will be made in accordance with Specification 55.2, Hauling.

### 53.2.5.2 Contractor Supply of Pit-Run

Payment will be made at the unit price bid per cubic metre for "Pit-Run Gravel - Supply and Place". This payment will be full compensation for supplying, placing and compacting the pit-run, and all labour, equipment, tools and incidentals necessary to complete the Work.

Payment for the supply of aggregate will be made in accordance with Specification 55.4, Supply of Aggregate.

# 53.2.5.3 Department Supply of Pit-Run

Payment will be made at the unit price bid per cubic metre for "Pit-Run Gravel - Pick up and Place". This payment will be full compensation for picking up, placing and compacting the pit-run material and all labour, equipment, tools and incidental necessary to complete the Work.

#### 53.2.6 WARRANTY

When pit-run gravel is used as part of another maintenance activity such as pavement patching, the warranty period for the pit-run gravel will be the same as the warranty period specified for the applicable activity. Otherwise, there is no warranty required for this Work.

1