

53.19 CLEANING RAISED MEDIANS

53.19.1 GENERAL

The Work consists of removing and disposing of sand, soil, salt residue and other debris from raised surface medians.

53.19.2 MATERIALS

The Contractor shall supply water required to "flush" the concrete surfaces.

53.19.3 EQUIPMENT

The Contractor shall supply all equipment necessary to complete the Work.

53.19.4 PROCEDURE

All Work shall be performed during daylight hours only, unless adequate lighting exists which provides visibility of at least 700 metres and prior approval of the Engineer is obtained. No Work shall be performed when the visibility is less than 700 metres.

Cleaning medians shall be completed prior to or in conjunction with roadway sweeping.

Cleaning operations shall proceed in the same direction as traffic and shall be carried out in a manner which prevents material from being cast into the flow of traffic or into drainage inlets.

Debris shall not be deposited on roadway surfaces or sidewalks.

After the removal of debris from the median surfaces, all concrete surfaces shall be flushed with water to remove salt residue.

53.19.5 TIME TO COMPLETE

The Contractor shall complete the Work within 30 calendar days of the issuance of the Work Order.

53.19.6 MEASUREMENT AND PAYMENT

Measurement will be in square metres of the surface area of raised median cleaned.

Payment will be made at the unit bid price bid per square metre for "Cleaning Raised Medians". This payment will be full compensation for removing and disposing of debris from the raised median, flushing the concrete surfaces with water and all labour, material, equipment, tools and incidentals necessary to complete the Work. Any sweeping of the roadway surface which is required solely as a result of cleaning the raised median is incidental to the Work.

53.19.7 WARRANTY

There is no warranty period for this Work.