

53.2 PIT-RUN GRAVEL

53.2.1 GENERAL

The Work consists of placing pit-run gravel on gravel surface roadways or in excavations for pavement patching or culvert installation work or at any other areas specified by the Engineer.

53.2.2 MATERIALS

The Contractor shall pick up pit-run from a source designated by the Engineer or produce designation 6, class 125 pit-run material in accordance with Specification 55.3, Aggregate Production and Stockpiling. In lieu of the designation 6, class 125 material, the Contractor may use a select, free draining material with a maximum top size of 125 mm, provided such material is satisfactory to the Engineer.

When required, the Contractor shall supply aggregate in accordance with Specification 55.4, Supply of Aggregate.

53.2.3 EQUIPMENT

The Contractor shall supply all equipment necessary to complete the Work.

53.2.4 PROCEDURE

All Work shall be performed during daylight hours only, unless adequate lighting exists which provides visibility of at least 700 metres and prior approval of the Engineer is obtained. No Work shall be performed when the visibility is less than 700 metres.

Traffic control and signing shall be performed in accordance with Specification 55.1, Traffic Accommodation and Temporary Signing.

Pit-run material shall be placed on the prepared area or in an excavation in a uniform manner and quantity, which will produce the required compacted thickness and width designated by the Engineer.

53.2.5 TIME TO COMPLETE AND SCHEDULING OF WORK

The Contractor shall complete the Work within 60 calendar days of the issuance of the Work Order and immediately following the Work required to excavate or prepare the area to be treated with pit-run. The Contractor shall diligently complete all aspects of the Work.

53.2.6 MEASUREMENT AND PAYMENT

Measurement will be in cubic metres based on the compacted volume of pit-run placed.

Payment will be made at the applicable unit price bid per cubic metre for "Pit-Run Gravel - Produce and Place" or "Pit-Run Gravel - Pick up and Place". This payment will be full compensation for either producing and placing or picking up and placing, compacting the pit-run, traffic accommodation and signing, and all labour, equipment, tools and incidentals necessary to complete the Work.

Payment for hauling will be made in accordance with Specification 55.2, Hauling.

Payment for the supply of aggregate will be made in accordance with Specification 55.4, Supply of Aggregate.

53.2.7 WARRANTY

The warranty period for this Work shall be 1 year.