

## **53.25 REMOVAL OF PAINTED ROADWAY LINES AND MESSAGES**

### **53.25.1 GENERAL**

The Work consists of removing painted roadway lines and messages from pavement surfaces.

### **53.25.2 MATERIALS**

The Contractor shall supply all materials necessary to complete the Work.

### **53.25.3 EQUIPMENT**

The Contractor shall supply all equipment necessary to complete the Work.

### **53.25.4 PROCEDURE**

All Work shall be performed during daylight hours only, unless adequate lighting exists which provides visibility of at least 700 metres and prior approval of the Engineer is obtained. No Work shall be performed when the visibility is less than 700 metres.

Traffic control and signing shall be performed in accordance with Specification 55.1, Traffic Accommodation and Temporary Signing.

The Contractor shall remove painted roadway lines and/or messages using methods and equipment which will not significantly damage the surface texture of the pavement and which will totally eliminate the pattern of the existing line or message. The methods and equipment used will be subject to the approval of the Engineer.

Covering the existing lines or messages with paint, liquid asphalt, or other materials will not be permitted.

The Contractor shall remove and dispose off all material or debris resulting from his operations.

### **53.25.5 TIME TO COMPLETE**

The Contractor shall complete the Work within 30 calendar days of the issuance of the Work Order.

### **53.25.6 MEASUREMENT AND PAYMENT**

Measurement will be in square metres of the area of the line or message removed.

Payment will be made at the unit price bid per square metre for "Removal of Painted Roadway Markings". This payment will be full compensation for removing pavement messages, traffic accommodation and signing, and all labour, material, equipment, tools and incidentals necessary to complete the Work.

### **53.25.7 WARRANTY**

There is no warranty period for this Work.