

53.26 MILLING OF MISCELLANEOUS AREAS

53.26.1 GENERAL

The Work consists of milling existing asphalt concrete pavement on miscellaneous areas and to the lines and dimensions specified by the Engineer.

53.26.2 EQUIPMENT

The Contractor shall supply all equipment required to complete the Work.

The equipment shall be capable of milling existing asphalt concrete pavement to an accurate depth of cut.

53.26.3 PROCEDURE

All Work shall be performed during daylight hours only, unless adequate lighting exists which provides visibility of at least 700 metres and prior approval of the Engineer is obtained. No Work shall be performed when the visibility is less than 700 metres.

Traffic control and signing shall be provided in accordance with Specification 55.1, Traffic Accommodation and Temporary Signing.

The designated area shall be milled to the depth specified in the Work Order. The adjacent road surface shall not be damaged.

The Contractor shall assume ownership of the cold milled material and shall remove it from the roadway.

On-site disposal of the material is subject to the approval of the Engineer.

53.26.4 TIME TO COMPLETE

The Contractor shall complete the Work within 60 calendar days of the issuance of the Work Order.

53.26.5 MEASUREMENT AND PAYMENT

Measurement for milling to depths less than or equal to 50 mm will be made in square metres of surface area milled. Measurement for milling beyond the 50 mm depth will be made in square metre-centimetre of the additional depth milled.

Payment will be made at the applicable unit price bid per square metre for "Milling of Miscellaneous Areas - Onsite Disposal (areas less than or equal to 50 mm depth)" or "Milling of Miscellaneous Areas - No Onsite Disposal (areas less than or equal to 50 mm depth)." Payment for milling beyond 50 mm in depth will be made at the applicable unit price bid per square metre-centimetre for "Milling of Miscellaneous Areas - Onsite Disposal (over 50 mm in depth)" or "Milling of Miscellaneous Areas - No Onsite Disposal (over 50 mm in depth)". These payments will be full compensation for milling the asphalt concrete pavement, removing and disposing of the milled material, traffic accommodation and signing and all labour, equipment, tools and incidentals necessary to complete the Work.

53.26.6 WARRANTY

There is no warranty period for this Work.