

## 53.36 SUPPLY AND ERECTION OF EMERGENCY SIGNS

### 53.36.1 GENERAL

The Work consists of maintaining, storing and erecting temporary signs dedicated solely for use in emergency situations as directed by the Engineer.

### 53.36.2 MATERIALS

The Department will supply the Contractor with the required number of Emergency Sign packages each containing the following signs. All signs shall be returned to the Department in good condition upon the termination of the Contract.

Sign	Reference Standard	Amount Required	
		2 Lane	Multi-Lane
Road Closed	WD116-2	8	16
Hazard Board	WD116-1R	8	16
Hazard Board	WD116-1L	8	16
Stands	WD116	8	16
Barricade Ahead	WD104	2	4
Flagman	WD-A-45	2	4
Detour (Tab)	WD-A-44	6	12
Detour Next - Kms	WD-103	2	4
-Pocket	WD-103	2	4
-Numbers	WD-103	2	4
Begin Detour 500 m	WD-102	2	4
Arrows	WD-116-5	6	12
Be Prepared To Stop	WD-111	2	4
Advance Speed Limit	RB-5	2	4
Maximum 50	RB-1	2	4
One Lane Traffic	WD-106	0	6
Keep Left	WD-161	0	6
Keep Right	WD-163	0	6
Two Way Traffic	WD-B-3	0	6
Two Way Traffic Tab	WD-B-3T	0	6
One Lane Traffic Do Not Pass	WD-159	0	6
Stop/Slow Paddles	TEB 1.14	2	4
Flashing Amber Lights	-	10	10
Replacement Batteries	-	10	10
Traffic Cones	71 cm	20	50

### 53.36.3 EQUIPMENT

The Contractor shall supply all equipment necessary to complete the Work.