

## **54.22 REMOVE AND DISPOSE OF GUARDRAIL, CABLE BARRIER AND POSTS**

### **54.22.1 GENERAL**

The Work consists of permanently removing and disposing of guardrail or cable barrier and posts. This specification only applies when guardrail or cable barrier is not being replaced.

### **54.22.2 MATERIALS**

The Contractor shall supply suitable material for backfilling of holes.

Unless otherwise directed by the Engineer (prior to issuing the Work Order), the Contractor shall assume ownership of all guardrail materials.

### **54.22.3 PROCEDURE**

The Contractor shall remove and dispose of guardrail and posts and/or cable barrier and posts as directed by the Engineer.

Holes shall be backfilled and compacted with material suitable to the Engineer and all excess debris (build up of sand) under the guardrail shall be removed and the site restored to match existing side slopes.

### **54.22.4 TIME TO COMPLETE**

The Contractor shall complete the Work within 60 days of the issuance of the Work Order.

### **54.22.5 ACCEPTANCE CRITERIA**

Evaluation of the Work will be based upon a visual inspection by the Engineer. The Work will be considered acceptable when the site has been left in a neat and tidy condition, all materials have been removed from the site, and the sideslopes are satisfactorily restored.

### **54.22.6 MEASUREMENT AND PAYMENT**

Measurement will be made in metres of the length of guardrail and/or barrier removed.

Payment will be made at the unit price bid per metre for "Guardrail/Barrier - Remove and Dispose". This payment will be full compensation for the removal and disposal of guardrail and/or barrier materials, removal and disposal of the posts, supplying backfill material and backfilling holes, cleanup of the disturbed

areas, and all labour, equipment, tools and incidentals necessary to complete the Work. Such payment will only be made in situations when the guardrail or cable barrier is not being replaced.

**54.22.7                      WARRANTY**

The warranty period for this Work is 60 days.

Settlement greater than 50 mm in disturbed areas occurring during the warranty period shall be repaired at the Contractor's expense.