

54.10 REPAIR CULVERT ENDS

54.10.1 GENERAL

The Work consists of excavating material around the culvert end and bending, cutting or otherwise reshaping the exposed culvert material to achieve its original intended shape.

54.10.2 MATERIALS

The Contractor shall supply all materials necessary to complete the Work.

54.10.3 EQUIPMENT

The Contractor shall supply all equipment necessary to complete the Work.

54.10.4 PROCEDURE

All Work shall be performed during daylight hours only. No Work shall be performed when the visibility is less than 700 metres.

Traffic control and signing shall be performed in accordance with Specification 55.1, Traffic Accommodation and Temporary Signing.

Riprap material shall be removed and salvaged where applicable.

Soil around the culvert end shall be excavated to the extent which allows repair of the pipe. The culvert end shall then be reshaped to its original intended shape. Salvaged riprap shall be reinstalled.

54.10.5 TIME TO COMPLETE

The Contractor shall complete the Work within 60 calendar days of the issuance of the Work Order.

54.10.6 MEASUREMENT AND PAYMENT

Measurement will be made of the number of sloped ends repaired.

Payment will be made at the unit price bid per sloped end for "Culvert End Repair". This payment will be full compensation for removing, salvaging and reinstalling riprap where applicable, excavating around the culvert end, reshaping the culvert end, traffic accommodation and signing and all labour, equipment, tools and incidentals necessary to complete the Work.

Payment for couplers when required will be made on an Extra Work basis in accordance with Specification 51.2, General(For Maintenance Work).

54.10.7 WARRANTY

There is no warranty period for this Work.