

## **54.21 LOCATING UNDERGROUND FACILITIES**

### **54.21.1 GENERAL**

The Work consists of locating and marking underground facilities owned by Alberta Transportation and Utilities at the locations specified by the Engineer. Generally the facility will be an electrical conduit in the vicinity of a traffic signal light or an illuminated overhead sign.

### **54.21.2 MATERIALS**

The Contractor shall supply all material required to mark the located facilities such as stakes, flags, or paint.

### **54.21.3 EQUIPMENT**

The Contractor shall supply all equipment necessary for the complete of the Work.

### **54.21.4 PROCEDURE**

Locating and marking of underground facility will be required whenever an excavation is to be done in the proximity of the facility.

The Contractor shall clearly mark the location of the facilities with paint or stakes with flags.

The Contractor shall supply the Engineer with a photograph of the completed Work.

The Contractor shall be responsible for all costs necessary to repair a facility which is damaged as a result of improper locating.

### **54.21.5 TIME TO COMPLETE**

All Work shall be completed within 2 calendar days of issuance of the Work Order

### **54.21.6 MEASUREMENT AND PAYMENT**

Measurement will be made of the number of hours required to complete the Work.

Payment will be made at the unit price bid per hour for "Locate Underground Facilities". This payment will be full compensation for all labour, material, equipment, tools and incidentals necessary to complete the Work.