

54.28 REPOSITION CONCRETE BARRIERS

54.28.1 GENERAL

The Work consists of repositioning concrete barriers which have been moved from their original position.

54.28.2 MATERIALS

No materials are required for this Work.

54.28.3 EQUIPMENT

The Contractor shall supply all necessary equipment to perform the Work.

54.28.4 PROCEDURE

Traffic control and signing shall be completed in accordance with Specification 55.1 Traffic Accommodation and Temporary Signing.

The Contractor shall reposition concrete barriers to their proper position as directed by the Engineer.

54.28.5 RESPONSE TIME AND TIME TO COMPLETE

In urgent situations, the Contractor shall respond within 2 hours of the issuance of the Work Order and diligently complete all aspects of the Work. In all other cases the Contractor shall complete the Work within 5 calendar days of the issuance of the Work Order.

54.28.6 MEASUREMENT AND PAYMENT

Measurement will be in hours for the time required to complete the Work.

Payment will be made at the unit price bid per hour for "Repositioning Concrete Barriers." This payment will be full compensation for repositioning concrete barriers, traffic accommodation and signing, and all labour, equipment, tools and incidentals necessary to complete the Work.

In urgent situations where the Contractor is required to respond the Work within 2 hours of the issuance of the Work Order, an additional payment will be made at the unit price bid per occurrence for "Concrete Barriers - Premium". This payment will be full compensation for complying with the accelerated scheduling required to complete the Work.

54.28.7 WARRANTY

There is no warranty period for this Work.