

54.33 PUMP OUT SEPTIC TANKS

54.33.1 GENERAL

The Work consists of pumping out and disposing of material from septic tanks and outdoor toilets located along primary highways at rest areas and truck turnouts.

54.33.2 MATERIALS

The Contractor shall supply all materials necessary to complete the Work. Water may be required to facilitate the removal of material from the septic tank.

54.33.3 EQUIPMENT

The Contractor shall supply all equipment necessary to complete the Work.

54.33.4 PROCEDURE

The number and locations of the septic tanks will be specified in the Special Provisions. The requirement for septic tank servicing shall be determined by the Engineer, or by the Contractor during the performance of other maintenance Work.

The tank shall be pumped out until the tank bottom is visible. The tank lids and/or valves shall then be secured. The area surrounding the tank shall be cleaned of any spills.

All waste material shall be hauled to and disposed of at a proper waste disposal site.

54.33.5 TIME TO COMPLETE

The Contractor shall complete the Work within 2 calendar days of the issuance of the Work Order.

54.33.6 MEASUREMENT AND PAYMENT

Measurement will be made of the number of septic tanks serviced.

Payment will be made at the unit price bid per tank for "Septic Tank - Pump and Clean". This payment will be full compensation for supplying any necessary water, removing, hauling and disposing of all waste material from the tank, cleaning the surrounding area, and all labour, materials, equipment, tools and incidentals necessary to complete the Work.

54.33.7 WARRANTY

There is no warranty period for this Work.