

USE IN ALL TENDERS SPECIFYING ASPHALT CONCRETE PAVEMENT (EPS)

(i) **AMENDMENT TO SPECIFICATION 3.50, ASPHALT CONCRETE PAVEMENT (EPS), RE: SAMPLING AND TESTING**

The contents of Subsection 3.50.4.5, **Re-testing Following Attempts to Improve Smoothness**, of Section 3.50.4, SAMPLING AND TESTING, are replaced in their entirety with the following:

When the test results on a Sublot of ACP indicate a penalty because of smoothness, the Contractor may make one attempt to improve the smoothness on the Sublot by additional work; in which case the following shall apply:

- (i) *The Contractor shall notify the Consultant in writing that he will make one attempt to improve smoothness.*
- (ii) *Additional work on a Sublot to improve smoothness shall be completed within 10 calendar days from the time the Contractor receives written notification from the Consultant indicating the smoothness test results for that Sublot.*

Sublots assessed to be in reject due to smoothness or bumps and dips greater than 8 mm shall be repaired as outlined in Subsection 3.50.6.3, End Product Rejection.

The Contractor shall not undertake any method of repair that is detrimental to the quality of the pavement. Any method of heating that has a detrimental effect on the pavement in the opinion of the Consultant, will not be allowed.

The Consultant will re-test any Sublots in which the Contractor has made one attempt to improve smoothness. The Sublot assessment for smoothness will be based upon the re-tested values.