

# USE IN ALL TENDERS SPECIFYING ASPHALT CONCRETE PAVEMENT - SUPERPAVE

(i) **AMENDMENT TO SPECIFICATION 3.53, ASPHALT CONCRETE PAVEMENT - SUPERPAVE, RE: SAMPLING AND TESTING**

The contents of Subsection 3.53.4.5, **Retesting Following Attempts to Improve Smoothness**, of Section 3.53.4, SAMPLING AND TESTING, are replaced in their entirety with the following:

*When the test results on a Sublot of ACP indicate a penalty because of smoothness, the Contractor may make one attempt to improve the smoothness on the Sublot by additional work; in which case the following shall apply:*

- (i) *The Contractor shall notify the Consultant in writing that he will make one attempt to improve smoothness.*
- (ii) *Additional work on a Sublot to improve smoothness shall be completed within 10 calendar days from the time the Contractor receives written notification from the Consultant indicating the smoothness test results for that Sublot.*

*Sublots assessed to be in reject due to smoothness or bumps and dips greater than 8 mm shall be repaired as outlined in Subsection 3.50.6.3, End Product Rejection.*

*The Contractor shall not undertake any method of repair that is detrimental to the quality of the pavement. Any method of heating that has a detrimental effect on the pavement in the opinion of the Consultant, will not be allowed.*

*The Consultant will re-test any Sublots in which the Contractor has made one attempt to improve smoothness. The Sublot assessment for smoothness will be based upon the re-tested values.*