

1.1 CONSTRUCTION CUT-OFF DATES FOR CEMENT STABILIZED BASE COURSE AND ASPHALT STABILIZED BASE COURSE

In addition to the provisions contained in Section 3.9.4.1 of Specification 3.9, Cement Stabilized Base Course, which remain in effect, placing of cement stabilized base course (CSBC) will not be permitted in any construction season after _____

The work on the project shall be organized in such a manner that if the CSBC is not completed by the seasonal cut-off date, the project shall be left in a safe condition, with the CSBC material lift terminating at the same location across the full width of the roadway, with an adequate ramp for traffic.

All Cement Stabilized Base Course placed during the construction season shall be covered with Asphalt Stabilized Base Course prior to seasonal shutdown.

Section 3.9.4.12, Application of Asphalt Stabilized Base Course shall be superseded by the following:

The time interval between the finishing and compacting of the Cement Stabilized Base Course and the placing of the Asphalt Stabilized Base Course shall be not less than ten days nor more than twenty days.

Application of the Asphalt Stabilized Base Course will be governed by Specification 3.5, Asphalt Stabilized Base Course.