

1.1 BRIDGE STRUCTURES - FINISHING APPROACHES

Construction of the bridge structure is currently underway by other forces, which work will run concurrently with work undertaken within the terms of this Contract.

The structures are scheduled to be available for traffic operation by _____.

The approaches to the separation structures, the limits of which are as shown on plan-profile sheets were previously constructed by other forces.

The completion of the previous work to the final gradeline and cross-section, including possible recompaction, trimming, clean-up, and preparing the surface for base course will not be paid for separately, but will be included in the unit prices bid for the applicable classes of excavation.