

ENVIRONMENTAL

- * Potential sites illustrated on adjacent board.
- * All work will be carried out in compliance with the Alberta Transportation Environmental Protection Plan (EPP) for the Planning and Construction of Water and Transportation Projects (January 9, 2009)
- * The contractor will develop a site specific Environmental Construction Operations (ECO) Plan - The ECO Plan is a Contractor's plan for the identification and mitigation of environmental impacts that may occur as a result of their activities and will include:
 - Erosion and Sediment Control (ESC) Plan - The Bow River is adjacent to the project area but will not be directly affected. An ESC Plan will be in place to minimize the potential for any indirect effects. No in-stream construction will be required on this project, and
 - Materials Handling Plan - A materials handling plan will include actions and procedures required for handling any contaminated water or soils that may be encountered during construction. As a general rule soil and groundwater within TUC will be submitted for analytical analysis prior to disposal to ensure applicable criteria is met.
- * Activities will be monitored and audits conducted as per approvals and guidelines through:
 - Self Regulatory Inspection,
 - Construction Monitoring
 - Post Construction Monitoring
 - ECO Plan Audits