




PLAN
1:20




ELEVATION
1:20




B SECTION
1:20



C SECTION
1:20




D SECTION
1:20




SPACER 'A' DETAIL
1:10


W-BEAM POST TYPE REFLECTOR COMPLETE WITH URETHANE HINGE AT 12000 MAX SPACING. REFLECTOR IS DOUBLE SIDED SHEETING 108 mm x 76 mm (MIN) MEETING ASTM D4956 TYPE IX OR XI FOR LUMINANCE LEVEL. SHEETING COLOR TO BE FLOURESCENT YELLOW OR WHITE TO MATCH PAVEMENT EDGE LINE.




ANCHOR BOLT ASSEMBLY DETAIL
1:5



POST DETAIL
1:10




P BENT PLATE DETAIL
1:10



ANCHOR PLATE AND ANCHOR BOLT TEMPLATE DETAIL
1:10

NOTE: ANCHOR BOLT TEMPLATE C/W NUTS AND ALIGNMENT NUTS TO BE INSTALLED DURING FABRICATION OF ANCHOR BOLT ASSEMBLIES. ANCHOR BOLT TEMPLATE AND ALIGNMENT NUTS TO BE REMOVED AFTER PLACING OF DECK CONCRETE AND PRIOR TO INSTALLATION OF W150x22 POST.



E SECTION
1:10

F SECTION
1:10

- GENERAL NOTES**
- ALL DIMENSIONS ARE IN MILLIMETRES UNLESS NOTED OTHERWISE.
 - RAILING CONFIGURATION IS BASED ON A RAILING CONFIGURATION THAT HAS BEEN CRASH TESTED AND MEETS THE REQUIREMENTS OF PERFORMANCE LEVEL 1 OF THE AASHTO GUIDE SPECIFICATIONS FOR BRIDGE RAILING, 1989.
 - RAILING SHALL NOT BE USED WITH CURB.
 - RAILING SHALL BE USED FOR CLEAR ROADWAYS LESS THAN 9.0 m ONLY.
 - DESIGN OF DECK REBAR SHALL BE CARRIED OUT ON A SITE SPECIFIC BASIS TO DEVELOP THE CAPACITY OF THE BRIDGERAIL POSTS, BASED ON $F_y = 350 \text{ MPa}$.

- FABRICATION**
- BRIDGERAIL, INCLUDING APPROACH RAIL TRANSITION, SHALL CONFORM TO THE CURRENT REQUIREMENTS OF THE SPECIFICATIONS FOR BRIDGE CONSTRUCTION SECTION 12 - BRIDGERAIL AND SECTION 14 - GUARDRAIL.
 - ALL PLATE STEEL AND STRUCTURAL SHAPES SHALL CONFORM TO CSA G40.21 GRADE 350W OR ASTM A36.
 - ALL ANCHOR BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A193 GRADE B7 ($F_y = 725 \text{ MPa}$, $F_u = 860 \text{ MPa}$). ALL NUTS AND WASHERS SHALL CONFORM TO A325. GALVANIZING SHALL STRICTLY FOLLOW THE FOLLOWING PROCEDURE WITH THE PRESENCE OF THE CONSULTANT:
 - BRUSH BLAST ANCHOR BOLTS TO REMOVE MILL SCALE AND OIL AFTER THREADING ENDS.
 - FLASH PICKLING NOT TO EXCEED 5 MINUTES.
 - QUICK DRY PRIOR TO HOT-DIP GALVANIZING (DO NOT STORE IN FLUX OR ACID RINSE).
 - ALL W-BEAM AND THRIE BEAM GUARDRAIL (INCLUDING W-THRIE BEAM TRANSITION SECTION) SHALL HAVE A MIN. YIELD STRENGTH OF 345 MPa.
 - TIMBER POSTS AND SPACERS SHALL BE COAST DOUGLAS FIR, PACIFIC COAST HEMLOCK OR LODGEPOLE PINE CONFORMING TO THE STRESS GRADE "SELECT STRUCTURAL POSTS AND TIMBERS" (NLGA PARAGRAPH 131 a).
 - ALL WELDING SHALL CONFORM TO CURRENT AWS SPECIFICATION D1.5.
 - ALL STEEL MATERIALS SHALL BE HOT-DIP GALVANIZED AFTER FABRICATION IN ACCORDANCE WITH ASTM A123/A123M AND ASTM F2329 UNLESS NOTED OTHERWISE.

- ERECTION**
- BRIDGERAIL ANCHOR BOLTS SHALL BE TIGHTENED AN ADDITIONAL 1/2 TURN OF THE NUT PAST THE "SNUG TIGHT" CONDITION.
 - ALL POSTS SHALL BE PERPENDICULAR TO GRADE.
 - ALL DIMENSIONS ARE MEASURED PARALLEL TO TOP OF BRIDGE DECK AND ALONG THE CENTRELINE OF ANCHOR BOLT ASSEMBLIES.
 - LINE AND ELEVATION OF RAIL SHALL HAVE A TOLERANCE OF 6 mm.
 - ALL NON-STANDARD GUARDRAIL LENGTHS SHALL BE SAW CUT TO SUIT AND ALL NON-STANDARD GUARDRAIL HOLES SHALL BE DRILLED. FLAME CUTTING OF GUARDRAIL SHALL NOT BE ALLOWED. APPLY TWO COATS OF ZINC RICH PAINT ON AREAS DAMAGED BY SAW CUTTING OR DRILLING.

NH 2011-12-22 S165300.rv3

		DESIGNER 	CHECKER 	RECOMMENDED DIRECTOR BRIDGE ENGINEERING ORIGINAL SIGNED BY REG QUINTON																	
PERMIT TO PRACTICE UMA ENGINEERING LTD. PERMIT NUMBER: P 5778 ORIGINAL SIGNED AND STAMPED BY: ART WASHUTA ON: NOVEMBER 21, 2000 <small>The Association of Professional Engineers, Geologists and Geophysicists of Alberta</small>		DATE _____	DATE _____	APPROVED EXECUTIVE DIRECTOR TECHNICAL STANDARDS BRANCH ORIGINAL SIGNED BY TIM HAWNT																	
ANCHOR BOLT ASSEMBLY DETAIL NOTE: ANCHOR BOLT ASSEMBLY SHALL BE MINIMUM 25 mm CLEAR FROM BOTTOM OF DECK.		<table border="1"> <thead> <tr> <th>REV</th> <th>DATE</th> <th>REVISIONS</th> <th>BY</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>2011-12-22</td> <td>REFLECTORS ADDED</td> <td></td> </tr> <tr> <td>2</td> <td>2007-02-14</td> <td>APPROACH RAIL HEIGHT</td> <td>RY</td> </tr> <tr> <td>3</td> <td>2004-03-01</td> <td>GENERAL NOTES</td> <td>RY</td> </tr> </tbody> </table>		REV	DATE	REVISIONS	BY	1	2011-12-22	REFLECTORS ADDED		2	2007-02-14	APPROACH RAIL HEIGHT	RY	3	2004-03-01	GENERAL NOTES	RY	DATE NOV 22, 2000	PL-1 LOW HEIGHT THRIE BEAM BRIDGERAIL
REV	DATE	REVISIONS	BY																		
1	2011-12-22	REFLECTORS ADDED																			
2	2007-02-14	APPROACH RAIL HEIGHT	RY																		
3	2004-03-01	GENERAL NOTES	RY																		
AI BAR CODE		DATE 2000-03-27	SHEET OF	DRAWING S-1653-00																	