




PLAN  
N.T.S.




ELEVATION  
N.T.S.



END VIEW  
Scale: 1"=1'-0"



CONNECTOR BOLT  
Scale: 1"=1'-0"




GIRDER FINISHES  
N.T.S.

MAX	SIZE	NO	TYPE	X'	Y'	LENGTH	WEIGHT
D601	6	8	D	4'-2		6'-2	74
D602	6	4	D	5'-0		7'-0	42
S301	3	368	C			1'-5	196
S401	4	21	str			39'-0	547
S402	4	138	B			6'-4	584
S501	5	278	str			4'-9	1377
T401	4	270	A			6'-0	1032
T601	6	4	D	4'-6		6'-6	39

TOTAL Lbs: 3,941

BAR TYPES  
(All bar dimensions are out to out)



GENERAL NOTES:

- DESIGN**  
A.A.S.H.O. 1965 Specification.  
A.C.I. 318 - 63 Shear Design, Fsp. = 5.67  
Loading: 0.90 of one wheel line of an H5 20 - 44 truck plus full dead load plus 2/2" wearing surface.
- MATERIALS**  
• Prestressing steel is 270 K 2'-4 - 7 wire strand.  
• Lightweight aggregates shall conform to the requirements of A.S.T.M. Specification C 330 with max. aggregate size 3/4". Min. 28 days compressive strength to be 5000 psi. Unit weight of the concrete shall be 120 lbs. per cubic foot plus or minus 5% in the plastic state. Entrained air shall be not less than 5%.
- FABRICATION**  
• Reinforcement: Diameters of all bends shall conform to the recommended sizes and all hooks, unless otherwise noted, shall conform to the recommended sizes detailed in the A.C.I. Manual of Standard Practice for Detailing Reinforced Concrete Structures.  
• Prestressing steel: Initial tensioning load = 28.9 kstrand Design Load = 20.7 kstrand  
• Concrete must attain 4250 p.s.i. compressive strength before the prestressing force is transferred.  
• Galvanizing shall be in accordance with A.S.T.M. Spec. A153.  
• Units are to conform to the requirements of the Alberta Bridge Branch Specification B190 - 64 for the Manufacture of Prestressed Concrete Bridge Units.
- ERECTION**  
• Lifting force at each hook must be vertical at all times.  
• Girder surface must be level at all times.

PRESTRESSED CONCRETE  
115'-0 TYPE FC-50A GIRDER  
LIGHTWEIGHT UNIT

GOVERNMENT OF THE PROVINCE OF ALBERTA  
DEPARTMENT OF HIGHWAYS  
BRIDGE BRANCH, EDMONTON

FILE NO. \_\_\_\_\_ HWY. NO. \_\_\_\_\_ DWS. NO. \_\_\_\_\_  
LOCATION \_\_\_\_\_ SCALE \_\_\_\_\_ OF \_\_\_\_\_  
STREAM \_\_\_\_\_ SHEET \_\_\_\_\_

NO.	DATE	DESCRIPTION	BY

DESIGNED BY T. BELKE DATE Oct. 28 1971  
 CHECKED BY N. FELPAK (L.K.) DATE Oct. 28 1971  
 CHECKED BY \_\_\_\_\_ DATE \_\_\_\_\_

20233  
 115'-0 TYPE FC-50A GIRDER LIGHTWEIGHT UNIT