








BAR LIST: FOR UNSKEWED GIRDER							
MARK	SIZE	NO.	TYPE	X	Y	LENGTH	WEIGHT
S 301	3	302	C			1'-6	170
S 401	4	21	STR.			32'-4	454
S 402	4	114	B			6'-4	482
S 501	5	226	STR.			4'-9	1120
T 401	4	158	A			4'-8	493
T 402	4	14	E			3'-0	28
T 601	6	4	D	4'-6		6'-6	39
D 601	6	6	D	4'-2		6'-2	56
D 602	6	4	D	5'-0		7'-0	42
T 403	4	118	F			1'-5	112
S 901	9	4	STR.			60'-0	816

TOTAL LBS: 3,812



GENERAL NOTES:

- DESIGN:
- A.A.S.H.O. 1960 SPECIFICATION EXCEPT ALLOWABLE FINAL CONCRETE STRESS = 420 P.S.I. IN TENSION.
  - LOADING: 8.10 OF ONE WHEEL LINE OF AN HS 20-44 TRUCK PLUS FULL DEAD LOAD PLUS 2" WEARING SURFACE.
- MATERIALS:
- CONCRETE SHALL BE OF STANDARD WEIGHT AGGREGATE WITH A MAXIMUM SIZE OF 3/4". MINIMUM COMPRESSIVE STRENGTH SHALL BE 5,000 P.S.I. AT 28 DAYS. ENTRAINED AIR SHALL BE NOT LESS THAN 3%.
  - PRESTRESSING STEEL SHALL BE 1/2" DIAMETER - 7 WIRE 270 K STRAND.
- FABRICATION:
- GIRDERS SHALL CONFORM TO THE REQUIREMENTS OF THE ALBERTA BRIDGE BRANCH SPECIFICATION S 190-44 FOR THE MANUFACTURE OF PRESTRESSED CONCRETE BRIDGE UNITS.
  - REINFORCEMENT: DIAMETERS OF ALL BENDS SHALL CONFORM TO THE RECOMMENDED MINIMUMS AND ALL HOOKS, UNLESS OTHERWISE NOTED, SHALL CONFORM TO THE RECOMMENDED SIZES DETAILED IN THE A.C.I. MANUAL OF STANDARD PRACTICE FOR DETAILING REINFORCED CONCRETE STRUCTURES.
  - PRESTRESSING STEEL: INITIAL TENSIONING LOAD = 28.91 K/STRAND DESIGN LOAD = 22.73 K/STRAND
  - CONCRETE MUST ATTAIN 4,500 P.S.I. COMPRESSIVE STRENGTH BEFORE THE PRESTRESSING FORCE IS TRANSFERRED.
  - GALVANIZING SHALL BE IN ACCORDANCE WITH ASTM SPECIFICATION A 153.
  - SHEAR KEYS AND BLOCKOUTS SHALL BE SANDBLAST ROUGHENED BY THE GIRDER FABRICATOR TO THE APPROVAL OF THE ENGINEER.
  - RIBS AND CONNECTOR BOLT HOLES SHALL BE OMITTED ON OUTSIDE LEGS OF EXTERIOR GIRDERS.
  - EXTERIOR GIRDER DIAPHRAGMS SHALL BE SPACED AT 12'-6 MAXIMUM.
  - CONNECTOR BOLTS, WASHERS, HEX NUTS, JAM NUTS AND ROODFOAM GASKETS SHALL BE SUPPLIED WITH THE GIRDERS.
- SECTION:
- LIFTING FORCE AT EACH HOOK MUST BE VERTICAL AT ALL TIMES. GIRDER SURFACE MUST BE LEVEL AT ALL TIMES.



APPROVED		PROVINCE OF ALBERTA DEPARTMENT OF HIGHWAYS AND TRANSPORT BRIDGE BRANCH	
26/1/73 REDRAWN FROM S-922 NO. DATE DESCRIPTION BY		PRESTRESSED CONCRETE 95'-0 TYPE FC-41" GIRDER	
REVISIONS			
DESIGNED	DRAWN BY	DATE	CHECKED BY
E.B.J.	V.G.B.	JAN./73	G.L. [Signature]
DATE		STREAM	LOCATION
APR. 73			
HWY. NO.	SCALE	FILE NO.	SHEET
	SHOWN		OF
			DWG. NO.
			S-922-73