

1.0 GENERAL

1.1 GENERAL

- .1 Perform final cleaning operations prior to the request for inspection for [Substantial Performance] [].
- .2 Remove surplus products, tools, construction machinery, and equipment not required for the performance of the remaining Work prior to the request for inspection for [Substantial Performance] [].
- .3 Remove waste products and debris resulting from the Work of the Contractor, and leave the Work clean and suitable for use by the Minister.
- .4 Repair, patch, and touch-up marred surfaces to match adjacent finishes.
- .5 Leave all surfaces in a neat, levelled condition.
- .6 Excavate and dispose of contaminated soils from equipment service and maintenance areas.
- .7 Excavate and dispose of excess soils including impervious, random, granular, and riprap materials.
- .8 Clean up and dispose of all foreign matter including wire, posts, logs, branches, roots, rocks, and construction debris.

2.0 PRODUCTS – NOT USED

3.0 EXECUTION – NOT USED

END OF SECTION